



**PAREX®**

# **Parex WaterMaster XPS CI**

Continuously Insulated System

Typical Details 2D

**BUILDING TRUST**



# Parex WaterMaster XPS CI

## Typical Details 2D

### Table of Contents


- |   |   |
|---|---|
| 1. Typical WaterMaster XPS CI Profile   | 19. Typical Window Head with Diverter Track (Flush)   |
| 2. Typical Application Over Framing   | 20. Typical Window Head Flashing with Sealant End Dam |
| 3. Typical Application over CMU   | 21. Typical Window Jamb (Flush)                       |
| 4. Typical Application over Brick   | 22. Typical Window Sill (Flush)                       |
| 5. Typical Aesthetic Reveal   | 23. Typical Window Head (Recessed)                    |
| 6. Typical Corner Mesh Application with Parex 355 Standard Intermediate 6 or 12 | 24. Typical Window Jamb (Recessed)                    |
| 7. Typical Pipe Penetration   | 25. Typical Window Sill (Recessed)                    |
| 8. Typical Light Fixture  | 26. Typical Flanged Window Head                       |
| 9. Typical Vertical Expansion Joint   | 27. Typical Flanged Window Jamb                       |
| 10. Typical Expansion Joint at Change in Substrate                              | 28. Typical Coping                                    |
| 11. Typical Expansion Joint at Floor Line                                       | 29. Typical Parapet Cap                               |
| 12. Typical Drainage at Floor Line  | 30. Typical Kick-Out Flashing at Sloped Roof          |
| 13. Typical Abutment to Brick with Drainage at Floor Line                       | 31. Typical Roof Edge Flashing                        |
| 14. Typical Termination at Foundation   | 32. Typical Section at Fascia - Soffit                |
| 15. Typical Abutment to Brick with Continuous Drainage Plane                    | 33. Typical Core Mounted Railing Attachment           |
| 16. Typical Termination at Foundation (Flush)                                   | 34. Typical Hand Rail Attachment                      |
| 17. Typical Window Head (Flush)   | 35. Typical Sign Attachment                           |
| 18. Typical Window Head with Weep Tubes (Flush)                                 |   |

### Notes:

- **The details within are the latest recommendations and are represent in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.**
- **Install Sika materials in accordance with current installation instructions.**
- **Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.**

## Parex WaterMaster XPS CI

### TYPICAL WATERMASTER XPS CI PROFILE



01 0525

(\*NOTE: BY OTHERS)


- Apply mixed Parex Adhesive/Base Coat to entire surface of insulation board using a stainless steel trowel with 1/2" x 1/2" (13 mm x 13 mm) notches spaced 2" (50 mm) apart. Ribbons of adhesive must be applied parallel to the 2' (610 mm) dimension of the XPS insulation board to ensure they are vertical when the XPS insulation board is applied to the substrate.
- Set XPS insulation board into place and apply pressure over entire surface of board to ensure positive uniform contact and high initial grab. Do not slide board into place.

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL APPLICATION OVER FRAMING



02 0525

(\*NOTE: BY OTHERS)


- All terminations must be fully encapsulated with mesh reinforced base coat. pre-backwrapping is recommended at drainage terminations. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Ensure a means for drainage is provided at system termination.
- Parex Joint/Transition Treatment Options: SikaWall MaxFlash, SikaWall Sheathing Fabric embedded in Parex WeatherSeal or SikaWall Flash Seal NP.

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL APPLICATION OVER CMU



03 0525

(\*NOTE: BY OTHERS)


- All terminations must be fully encapsulated with mesh reinforced base coat. pre-backwrapping is recommended at drainage terminations. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Ensure a means for drainage is provided at system termination.
- Parex Transition Treatment Options: SikaWall MaxFlash, SikaWall Sheathing Fabric embedded in Parex WeatherSeal or SikaWall Flash Seal NP.

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL APPLICATION OVER BRICK



- All terminations must be fully encapsulated with mesh reinforced base coat. pre-backwrapping is recommended at drainage terminations. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Ensure a means for drainage is provided at system termination.
- Parex Transition Treatment Options: SikaWall MaxFlash, SikaWall Sheathing Fabric embedded in Parex WeathertSeal or SikaWall Flash Seal NP.

04 0525


(\*NOTE: BY OTHERS)

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

# Parex WaterMaster XPS CI

## TYPICAL AESTHETIC REVEAL



- Maintain a continuous layer of XPS insulation board, at a minimum 3/4" (19 mm) thickness, behind all reveals and aesthetic grooves.
- Reinforcing mesh shall be continuous and care shall be taken to ensure reinforcing mesh is not cut during base coat application.
- Horizontal reveals shall provide for outward positive drainage.
- Reveals must not occur at the abutment of two pieces of XPS insulation board.

05 0525


(\*NOTE: BY OTHERS)

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL CORNER MESH APPLICATION WITH PAREX 355 STANDARD INTERMEDIATE 6 OR 12



06 0525

(\*NOTE: BY OTHERS)

- Ensure Parex 355 Standard, SikaWall Intermediate 6 or SikaWall Intermediate 12 Reinforcing Mesh is lapped a minimum of 8" (203 mm) around corners.
- SikaWall Corner Mesh on outside corner can be replaced, with Parex 355 Standard, SikaWall Intermediate 6 or SikaWall Intermediate 12, extended a minimum of 8" (203 mm) around corner from both sides (creating double layer of mesh at corner).
- Parex Joint Treatment Options: SikaWall MaxFlash, SikaWall Sheathing Fabric embedded in Parex WeatherSeal or SikaWall Flash Seal NP.


The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.



## Parex WaterMaster XPS CI

### TYPICAL PIPE PENETRATION



07 0525

(\*NOTE: BY OTHERS)


- All terminations must be fully encapsulated with mesh reinforced basecoat. Pre-backwrap both the vertical and horizontal terminations. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Ensure all penetrations into the system are properly sealed. Reference *Acceptable Sealants to use with Parex Wall Systems* Technical Bulletin for a list of sealants.
- Provide continuous air seal around perimeter of penetration prior to XPS insulation board application. Reference *Acceptable Sealants for use with Parex Weather Seal* Technical Bulletin for a list of sealants.
- Do not apply finish to areas that will receive sealant.

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL LIGHT FIXTURE



08 0525

(\*NOTE: BY OTHERS)


- All terminations must be fully encapsulated with mesh reinforced base coat. Pre- backwrap both the vertical and horizontal terminations. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Ensure all penetrations into the system are properly sealed.
- Reference *Acceptable Sealants to use with Parex Wall Systems* Technical Bulletin for a list of sealants.
- Provide continuous air seal around perimeter of penetration prior to XPS insulation board application. Reference *Acceptable Sealants for use with Parex WeatherSeal* Technical Bulletin for a list of sealants.

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL VERTICAL EXPANSION JOINT



09 0525

(\*NOTE: BY OTHERS)


- All terminations must be fully encapsulated with mesh reinforced base coat. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Do not apply finish to areas that will receive sealant.
- Ensure drainage plane is continuous and unobstructed at expansion joint.
- Typical locations for system expansion joints are at building expansion joints, at prefabricated panel joints, floor lines of wood frame construction or where slip tracks are used in steel frame construction, where substrates change and where structural movement is anticipated. It is the sole responsibility of the project design team, including the architect, engineer, etc., to ultimately determine specific expansion joint placement, width and design. Detail specific locations in construction drawings
- Provide sufficient slack in SikaWall Flash Seal NP at expansion joint to allow for movement.
- Reference *Acceptable Sealants for use with Parex Wall Systems* Technical Bulletin for a list of sealants.

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL EXPANSION JOINT AT CHANGE IN SUBSTRATE



- All terminations must be fully encapsulated with mesh reinforced base coat. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Do not apply finish to areas that will receive sealant.
- Ensure drainage plane is continuous and unobstructed at expansion joint.
- Typical locations for system expansion joints are at building expansion joints, at prefabricated panel joints, floor lines of wood frame construction or where slip tracks are used in steel frame construction, where substrates change and where structural movement is anticipated. It is the sole responsibility of the project design team, including the architect, engineer, etc., to ultimately determine specific expansion joint placement, width and design. Detail specific locations in construction drawings.
- Provide sufficient slack in SikaWall Flash Seal NP at expansion joint to allow for movement.
- Reference *Acceptable Sealants for use with Parex Wall Systems* Technical Bulletin for a list of sealants.

10 0525


(\*NOTE: BY OTHERS)

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL EXPANSION JOINT AT FLOOR LINE



11 0525

(\*NOTE: BY OTHERS)


- All terminations must be fully encapsulated with mesh reinforced base coat. pre-backwrapping is recommended at drainage terminations. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Do not apply finish to areas that will receive sealant.
- Provide sufficient slack in the SikaWall Flash Seal NP at expansion joint to allow for movement.
- Typical locations for system expansion joints are at building expansion joints, at prefabricated panel joints, floor lines of wood frame construction or where slip tracks are used in steel frame construction, where substrates change and where structural movement is anticipated. It is the sole responsibility of the project design team, including the architect, engineer, etc., to ultimately determine specific expansion joint placement, width and design. Detail specific locations in construction drawings.
- It is recommended that a means for drainage is provided at every third floor. (See typical drainage at floorline detail).
- Ensure drainage plane is continuous and unobstructed at expansion joint.
- Reference *Acceptable Sealants for use with Parex Wall Systems* Technical Bulletin for a list of sealants.

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

# Parex WaterMaster XPS CI

## TYPICAL DRAINAGE AT FLOOR LINE



12 0525

(\*NOTE: BY OTHERS)


- All terminations must be fully encapsulated with mesh reinforced base coat. pre-backwrapping is recommended at drainage terminations. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Do not apply finish to areas that will receive sealant.
- Typical locations for system expansion joints are at building expansion joints, at prefabricated panel joints, floor lines of wood frame construction or where slip tracks are used in steel frame construction, where substrates change and where structural movement is anticipated. It is the sole responsibility of the project design team, including the architect, engineer, etc., to ultimately determine specific expansion joint placement, width and design. Detail specific locations in construction drawings.
- It is recommended that a means for drainage is provided at every third floor.
- Provide sufficient slack in the SikaWall Flash Seal NP at expansion join to allow for movement.
- Parex Transition Treatment Options: SikaWall MaxFlash, SikaWall Sheathing Fabric embedded in Parex WeatherSeal or SikaWall Flash Seal NP.
- Reference Acceptable Sealants for Use With Sika Facades Technical Bulletin for a list of sealants.

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL ABUTMENT TO BRICK WITH DRAINAGE AT FLOOR LINE



13 0525

(\*NOTE: BY OTHERS)


- All terminations must be fully encapsulated with mesh reinforced base coat. pre-backwrapping is recommended at drainage terminations. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Ensure a means for drainage is provided at system termination at brick.
- Brick must be installed per local code requirements.
- Provide sufficient slack in the SikaWall Flash Seal NP at expansion joint to allow for movement.
- Parex Transition Treatment Options: SikaWall MaxFlash, SikaWall Sheathing Fabric embedded in Parex WeatherSeal or SikaWall Flash Seal NP.

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL TERMINATION AT FOUNDATION



14 0525

(\*NOTE: BY OTHERS)

- All terminations must be fully encapsulated with mesh reinforced base coat. pre-backwrapping is recommended at drainage terminations. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Ensure a means for drainage is provided at system termination at foundation.
- Terminate system a minimum of 6" (152 mm) above grade.
- Extend system a minimum of 2" (50 mm) and a maximum of 12" (305 mm) at the sole plate foundation transition.
- Apply Parex Transition Treatment at transition from sheathing to concrete (behind flashing).
- Parex Transition Treatment Options: SikaWall MaxFlash, SikaWall Sheathing Fabric embedded in Parex WeatherSeal or SikaWall Flash Seal NP.


The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.



## Parex WaterMaster XPS CI

### TYPICAL ABUTMENT TO BRICK WITH CONTINUOUS DRAINAGE PLANE



15 0525

(\*NOTE: BY OTHERS)


- All terminations must be fully encapsulated with mesh reinforced base coat. pre-backwrapping is recommended at drainage terminations. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Ensure a continuous drainage plane is maintained at system abutment to brick.
- Brick must be installed per local code requirements.
- Reference *Acceptable Sealants for use with Parex Wall Systems* Technical Bulletin for a list of sealants.

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL TERMINATION AT FOUNDATION (FLUSH)



16 0525

(\*NOTE: BY OTHERS)


- All terminations must be fully encapsulated with mesh reinforced base coat. pre-backwrapping is recommended at drainage terminations. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Ensure a means for drainage is provided at system termination at foundation.
- Place weep tubes a maximum of 24" (610 mm) on center.
- Do not apply finish to areas that will receive sealant.
- Reference Acceptable Sealants for use with Parex Wall System Technical Bulletin for a list of sealants.

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL WINDOW HEAD (FLUSH)



17 0525

(\*NOTE: BY OTHERS)


- All terminations must be fully encapsulated with mesh reinforced base coat. pre-backwrapping is recommended at drainage terminations. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Ensure a means for drainage is provided at system termination at window head.
- Provide end-dams at flashing terminations.
- Parex Transition Treatment Options: SikaWall MaxFlash, SikaWall Sheathing Fabric embedded in Parex or SikaWall Flash Seal NP.
- Prior to window and XPS installation, ensure water-resistive barrier is properly applied into the rough openings in accordance with Parex application guidelines and code requirements. Reference Parex WeatherSeal published typical details.
- Consult window and sealant manufacturers to verify window installation, detailing and to ensure no water leakage into the wall assembly.

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL WINDOW HEAD WITH WEEP TUBES (FLUSH)



18 0525

(\*NOTE: BY OTHERS)


- All terminations must be fully encapsulated with mesh reinforced base coat. pre-backwrapping is recommended at drainage terminations. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Ensure a means for drainage is provided at system termination at window head.
- Provide end-dams at flashing terminations.
- Do not apply finish to areas that will receive sealant.
- Parex Transition Treatment Options: SikaWall MaxFlash, SikaWall Sheathing Fabric embedded in Parex or SikaWall Flash Seal NP.
- Prior to window and XPS installation, ensure water-resistive barrier is properly applied into the rough openings in accordance with Parex application guidelines and code requirements. Reference Parex WeatherSeal published typical details.
- Place weep tubes a maximum of 16" (406 mm) on center.
- Reference *Acceptable Sealants for use with Parex Wall Systems* Technical Bulletin for a list of sealants.
- Consult window and sealant manufacturers to verify window installation, detailing and to ensure no water leakage into the wall assembly.

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL WINDOW HEAD WITH DIVERTER TRACK (FLUSH)



- All terminations must be fully encapsulated with mesh reinforced base coat. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board
- Provide a back wrapped type joint with backer rod and sealant at system terminations to dissimilar materials, ensuring that a water tight seal is achieved (width per design).
- Diverter Flashing Requirements:
  - Extend diverter flashing 6" (152 mm) beyond opening on either side of the opening to allow potential moisture to drain down the wall to the side of the opening.
  - Ensure the flashing is in one piece and does not exceed 10 ft.
  - Ensure the diverter track flashing is sloped 1-2" to provide a means for drainage.
- Parex Transition Treatment Options: SikaWall MaxFlash, SikaWall Sheathing Fabric embedded in Parex WeatherSeal or SikaWall Flash Seal NP.
- Maintain a minimum of 3/4" (19 mm) XPS insulation thickness.
- Prior to window and XPS installation, ensure water-resistive barrier is properly applied into the rough openings in accordance with Parex application guidelines and code requirements. Reference Parex WeatherSeal published typical details.
- Reference *Acceptable Sealants for use with Parex Wall Systems* Technical Bulletin for a list of sealants.
- Do not apply finish in areas that will receive sealant.
- Consult window and sealant manufacturers to verify window installation, detailing and to ensure no water leakage into the wall assembly.

19 0525


(\*NOTE: BY OTHERS)

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL WINDOW HEAD FLASHING WITH SEALANT END DAM



20 0525

(\*NOTE: BY OTHERS)


- Parex Transition Treatment Options: SikaWall MaxFlash, SikaWall Sheathing Fabric embedded in Parex WeatherSeal or SikaWall Flash Seal NP.
- Consult window and sealant manufacturers to verify window installation, detailing and to ensure no water leakage into the wall assembly.
- Prior to window and XPS installation, ensure water-resistive barrier is properly applied to the rough openings in accordance with Parex application guidelines and code requirements. Reference Parex WeatherSeal published typical details.
- Reference *Acceptable Sealants for use with Parex Wall Systems* Technical Bulletin for a list of sealants.
- Do not apply finish in areas that will receive sealant.
- All terminations must be fully encapsulated with mesh reinforced base coat. pre-backwrapping is recommended at drainage terminations. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL WINDOW JAMB (FLUSH)



21 0525

(\*NOTE: BY OTHERS)


- All terminations must be fully encapsulated with mesh reinforced base coat. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board
- Prior to window and XPS installation, ensure water-resistive barrier is properly applied into the rough openings in accordance with Parex application guidelines and code requirements. Reference Parex WeatherSeal published typical details for further information.
- Do not apply finish to areas that will receive sealant.
- Provide a back wrapped type joint with backer rod and sealant at system terminations to dissimilar materials, ensuring that a water tight seal is achieved (width per design).
- Parex Transition Treatment Options: SikaWall MaxFlash, SikaWall Sheathing Fabric embedded in Parex WeatherSeal or SikaWall Flash Seal NP.
- Reference *Acceptable Sealants for use with Parex Wall Systems* Technical Bulletin for a list of sealants.
- Consult window and sealant manufacturers to verify window installation, detailing and to ensure no water leakage into the wall assembly.

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL WINDOW SILL (FLUSH)



22 0525

(\*NOTE: BY OTHERS)

- All terminations must be fully encapsulated with mesh reinforced base coat. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Prior to window and XPS installation, ensure water-resistive barrier is properly applied to the rough openings in accordance with Parex application guidelines and code requirements. Reference Parex WeatherSeal published typical details.
- Do not apply finish to areas that will receive sealant.
- Provide a back wrapped type joint with backer rod and sealant at system terminations to dissimilar materials, ensuring that a water tight seal is achieved (width per design).
- Parex Transition Treatment Options: SikaWall MaxFlash, SikaWall Sheathing Fabric embedded in Parex WeatherSeal or SikaWall Flash Seal NP.
- Reference *Acceptable Sealants for use with Parex Wall Systems* Technical Bulletin for a list of sealants.
- Consult window and sealant manufacturers to verify window installation, detailing and to ensure no water leakage into the wall assembly.


The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.



## Parex WaterMaster XPS CI

### TYPICAL WINDOW HEAD (RECESSED)



23 0525

(\*NOTE: BY OTHERS)


- All terminations must be fully encapsulated with mesh reinforced base coat. pre-backwrapping is recommended at drainage terminations. Extend reinforcing mesh a minimum 2 1/2" onto back of insulation board.
- Do not apply finish to areas that will receive sealant.
- Ensure a means for drainage is provided at system termination at window head.
- Provide a back wrapped type joint with backer rod and sealant at system terminations to dissimilar materials, ensuring that a water tight seal is achieved (width per design).
- Prior to window and XPS installation, ensure water-resistive barrier is properly applied into the rough openings in accordance with Parex application guidelines and code requirements. Reference Parex WeatherSeal published typical details for further information.
- Consult window and sealant manufacturers to verify window installation, detailing and to ensure no water leakage into the wall assembly.
- Reference *Acceptable Sealants for Use with Parex Wall Systems* Technical Bulletin for a list of sealants.

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL WINDOW JAMB (RECESSED)



24 0525

(\*NOTE: BY OTHERS)


- All terminations must be fully encapsulated with mesh reinforced base coat. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Prior to window and XPS installation, ensure water-resistive barrier is properly applied into the rough openings in accordance with Parex application guidelines and code requirements. Reference Parex WeatherSeal published typical details for further information.
- Do not apply finish to areas that will receive sealant.
- Provide a back wrapped type joint with backer rod and sealant at system terminations to dissimilar materials, ensuring that a water tight seal is achieved (width per design).
- Parex Transition Treatment Options: SikaWall Flash Seal MaxFlash, SikaWall Sheathing Fabric embedded in Parex WeatherSeal or SikaWall NP.
- Reference *Acceptable Sealants for use with Parex Wall Systems* Technical Bulletin for a list of sealants.
- Consult window and sealant manufacturers to verify window installation, detailing and to ensure no water leakage into the wall assembly.

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL WINDOW SILL (RECESSED)



25 0525

(\*NOTE: BY OTHERS)


- All terminations must be fully encapsulated with mesh reinforced base coat. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Ensure water-resistive barrier is properly applied into the rough openings in accordance with application guidelines and code requirements prior to XPS insulation board application.
- Ensure that metal pan flashing extends onto the system a minimum of 2" (50 mm) down the face and that end dams are provided.
- Parex Transition Treatment Options: SikaWall MaxFlash, SikaWall Sheathing Fabric embedded in Parex WeatherSeal or SikaWall Flash Seal NP.
- Reference *Acceptable Sealants for use with Parex Wall Systems* Technical Bulletin for a list of sealants.
- Consult window and sealant manufacturers to verify window installation, detailing and to ensure no water leakage into the wall assembly

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL FLANGED WINDOW HEAD



26 0525

(\*NOTE: BY OTHERS)


- All terminations must be fully encapsulated with mesh reinforced base coat. pre-backwrapping is recommended at drainage terminations. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Ensure the window flange is treated with a Parex transition treatment.
- Ensure a means for drainage is provided at system termination at window head.
- Parex Transition Treatment Options: SikaWall MaxFlash, SikaWall Sheathing Fabric embedded in Parex WeatherSeal or SikaWall Flash Seal NP.
- Prior to window and XPS installation, ensure water-resistive barrier is properly applied into the rough openings in accordance with Parex application guidelines and code requirements. Reference Parex WeatherSeal published typical details for further information.
- Consult window and sealant manufacturers to verify window installation, detailing and to ensure no water leakage into the wall assembly.

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL FLANGED WINDOW JAMB



27 0525

(\*NOTE: BY OTHERS)


- All terminations must be fully encapsulated with mesh reinforced base coat. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Ensure the window flange is treated with a Parex transition treatment.
- Parex Transition Treatment Options: SikaWall MaxFlash, SikaWall Sheathing Fabric embedded in Parex WeatherSeal or SikaWall Flash Seal NP.
- Do not apply finish to areas that will receive sealant.
- Provide a back wrapped type joint with backer rod and sealant at system terminations to dissimilar materials, ensuring that a water tight seal is achieved (width per design).
- Prior to window and XPS installation, ensure water-resistive barrier is properly applied into the rough openings in accordance with Parex application guidelines and code requirements. Reference Parex WeatherSeal published typical details.
- Consult window and sealant manufacturers to verify window installation, detailing and to ensure no water leakage into the wall assembly.

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL COPING



- All terminations must be fully encapsulated with mesh reinforced base coat. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Ensure that metal coping/ flashing extends onto the system a minimum of 2" (50 mm) down the face.
- Extend Parex WeatherSeal or SikaWall MaxFlash onto bottom of blocking or provide alternate air seal at sheathing termination to blocking.
- Reference *Acceptable Sealants for use with Parex Wall Systems* Technical Bulletin for a list of sealants.

28 0525


(\*NOTE: BY OTHERS)

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL PARAPET CAP



29 0525

(\*NOTE: BY OTHERS)


- All terminations must be fully encapsulated with mesh reinforced base coat. pre-backwrapping is recommended at drainage terminations. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Provide a minimum 6:12 slope for all horizontal surfaces. Parex requires the use of a roofing system or metal cap flashing for sloped surfaces over 24" (610 mm).
- Additional layers of mesh reinforced base coat is recommended when sloped surfaces exceed 12" (305 mm).
- Ensure a means for drainage is provided at system termination.
- Terminate system a minimum of 8" (203 mm) above flat roof. Roofing material shall not extend above the flashing flange.
- Maintain a minimum 1" (25 mm) thick XPS insulation board.
- Parex Joint Treatment Options: SikaWall MaxFlash, SikaWall Sheathing Fabric embedded in Parex WeatherSeal or SikaWall Flash Seal NP.
- Reference *Acceptable Sealants for use with Parex Wall Systems* Technical Bulletin for a list of sealants.

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL KICK-OUT FLASHING AT SLOPED ROOF



30 0525

(\*NOTE: BY OTHERS)

- All terminations must be fully encapsulated with mesh reinforced base coat. pre-backwrapping is recommended at drainage terminations. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Ensure a means for drainage is provided at system termination at roof.
- Terminate system a minimum of 2" (50 mm) above sloped roof.
- Ensure step flashing is a minimum of 2" (50 mm) behind system.
- Kick-out flashing shall be a minimum of 4" (102 mm) in height.
- Do not apply finish to areas that will receive sealant.
- Parex Transition Treatment Options: SikaWall MaxFlash, SikaWall Sheathing Fabric embedded in Parex WeatherSeal or SikaWall Flash Seal NP.
- Reference *Acceptable Sealants for use with Parex Wall Systems Technical Bulletin* for a list of sealants.


The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.



## Parex WaterMaster XPS CI

### TYPICAL ROOF EDGE FLASHING



31 0525

(\*NOTE: BY OTHERS)


- All terminations must be fully encapsulated with mesh reinforced base coat. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Ensure that metal coping/flashings extends onto the system a minimum of 2" (50 mm) down the face.
- Extend Parex WeatherSeal or SikaWall MaxFlash onto bottom of blocking or provide alternate air seal at sheathing termination to blocking.
- Reference *Acceptable Sealants for use with Parex Wall Systems* Technical Bulletin for a list of sealants.

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

# Parex WaterMaster XPS CI

## TYPICAL SECTION AT FASCIA - SOFFIT



\*BY OTHERS

- All terminations must be fully encapsulated with mesh reinforced base coat. Pre-backwrap both the vertical and horizontal terminations. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Extend Parex WeatherSeal a minimum of 4" (100mm) onto soffit. If necessary for air barrier continuity Parex WeatherSeal can be applied over entire soffit.
- Ensure a means of drainage is provided at system termination at soffit/fascia transition.

32 0525


(\*NOTE: BY OTHERS)

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL CORE MOUNTED RAILING ATTACHMENT



- All terminations must be fully encapsulated with mesh reinforced base coat. Pre-backwrap both the vertical and horizontal terminations. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Ensure all penetrations into the system are properly sealed.
- Reference *Acceptable Sealants for use with Parex Wall Systems* Technical Bulletin for a list of sealants.

33 0525


(\*NOTE: BY OTHERS)

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL HAND RAIL ATTACHMENT



\*BY OTHERS

- All terminations must be fully encapsulated with mesh reinforced base coat. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Ensure all penetrations into the system are properly sealed.
- Reference *Acceptable Sealants for use with Parex Wall Systems* Technical Bulletin for a list of sealants.

34 0525


(\*NOTE: BY OTHERS)

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.

## Parex WaterMaster XPS CI

### TYPICAL SIGN ATTACHMENT



\*BY OTHERS

35 0525

(\*NOTE: BY OTHERS)

- All terminations must be fully encapsulated with mesh reinforced base coat. Extend reinforcing mesh a minimum of 2 1/2" onto back of insulation board.
- Ensure all penetrations into the system are properly sealed.
- Reference *Acceptable Sealants for use with Parex Wall Systems* Technical Bulletin for a list of sealants.

The details within are the latest recommendations and are represented in good faith by Sika Corporation US (hereinafter Sika). The details are subject to change without notice. Sika accepts no liability for the end use of the details. For conditions not shown, consult Sika for review of specific details.

- Install Sika materials in accordance with current installation instructions.
- Unsatisfactory conditions shall be reported to the General Contractor and corrected before the application of Sika products.



**BUILDING TRUST**



## **LIMITED WARRANTY NOTICE**

Prior to each use of any product of Sika Corporation, its subsidiaries or affiliates ("SIKA"), the user must always read and follow the warnings and instructions on the product's most current product label, Product Data Sheet and Safety Data Sheet which are available at [usa.sika.com/parex](http://usa.sika.com/parex) or by calling our Technical Service Department at +1 (800) 226-2424.

Nothing contained in any SIKA literature or materials relieves the user of the obligation to read and follow the warnings and instructions for each SIKA product as set forth in the current product label, Product Data Sheet and Safety Data Sheet prior to use of the SIKA product.

SIKA warrants this product for one year from date of installation to be free from manufacturing defects and to meet the technical properties on the current Product Data Sheet if used as directed within the product's shelf life. User determines suitability of product for intended use and assumes all risks. User's and/or buyer's sole remedy shall be limited to the purchase price or replacement of this product exclusive of any labor costs. NO OTHER WARRANTIES EXPRESS OR IMPLIED SHALL APPLY INCLUDING ANY WARRANTY OF MERCHANTABILITY OR FITNESS FOR A PARTICULAR PURPOSE. SIKA SHALL NOT BE LIABLE UNDER ANY LEGAL THEORY FOR SPECIAL OR CONSEQUENTIAL DAMAGES. SIKA SHALL NOT BE RESPONSIBLE FOR THE USE OF THIS PRODUCT IN A MANNER TO INFRINGE ON ANY PATENT OR ANY OTHER INTELLECTUAL PROPERTY RIGHTS HELD BY OTHERS. Sale of SIKA products are subject to the Terms and Conditions of Sale which are available at [usa.sika.com](http://usa.sika.com).

For the most current version of this literature, please visit our website at [usa.sika.com/parex](http://usa.sika.com/parex).

**Sika Corporation**

201 Polito Avenue  
Lyndhurst, NJ 07071 USA  
Customer Service +1 (800) 433-9517  
Technical Service +1 (800) 226-2424  
[usa.sika.com/parex](http://usa.sika.com/parex)

Rev May 2025

**BUILDING TRUST**

