## 5 FT MEMBRANE FASTENING FOR SIKA SARNAFIL ACCEPTED NON-F.M. INSURED PROJECTS

PERIMETER-DETERMINED AS 0.10 x LEAST PLAN WIDTH OR 0.40 OF BUILDING HEIGHT, WHICH EVER IS LESS-MINIMUM OF TWO-5FT. WIDE SHEETS OF MEMBRANE INSTALLED ALONG THE PERIMETER. CORNER AREAS WHERE PERIMETER SHEETS INTERSECT, ADD ROWS OF SARNAFASTENERS AND SARNADISCS/RAILS OVER THE TOP OF THE MEMBRANE AND WELD A COVERSTRIP ABOVE THEM FOR WATERTIGHTNESS. THE FASTENING RATE ALONG THE PERIMETER SHALL BE 6 INCHES CLOSER THAN THE FIELD FASTENING PATTER.

